

## Addendum No. 2

### TMWA Main Relocation – Reno 2008 Street / Sewer Rehab

### Contract No. 0607-213

### PWP #WA-2007-265

The following information is clarifications to the questions received and by reference incorporated into the bid document for the above referenced project. The bid dates and times remain the same.

1. **Is this project Federally funded in any way?** No
2. **If the project is federally funded and requires excess materials to be disposed at a permitted /approved site, does TMWA have any permitted/approved sites that require the material?** n/a
3. **Will you provide a list of the required permits and permit fees that TMWA will pay or not pay?**  
TMWA is responsible for the Excavation and Encroachment Permit Fee. The contractor is responsible for all other permit fees.
4. **Please provide a copy of the soils report.** A soils investigation was not done. There is no soils report.
5. **At the jobsite walk, an overlay of a portion or all of Mt Rose was discussed. Will this be added to the bid schedule or covered by change order?** The issue of the overlay will be addressed either by a change order or will be included in the City of Reno Sanitary Sewer contract
6. **The existing roads appear to be very worn, with substantial cracking. In the likely event that asphalt outside the trench patch fails as a result of the work and the quantity of patching increases, will this be paid by force account/change order? To what extent will the contractor be required replace the additional failed area? AC only? Partial road section? Full section?** The existing roadway surfaces are in very poor condition. The Contractor is required to saw cut the pavement and confine the excavation to a minimum. Payment for the Temporary AC patch is to be included in Bid Item No. 3, Water Main Trench Excavation, Bedding, Backfill and Temporary AC Pavement Patch.

If there are areas damaged outside the normal trench width through no fault of the Contractor, as determined by the TMWA Inspector, payment for additional Temporary Patch will be made by Bid Item 54.C-16, Furnish and Place 3-inch Temporary Asphalt Concrete Patch.

As noted in the Excavation/Encroachment Permit, All trenching will be with excavators, backhoes or similar equipment. A "rock wheel" is not permitted. If track equipment is used, it shall be the responsibility of the Contractor to protect the existing asphalt and concrete. This is interpreted by TMWA to mean collateral damage to asphalt and concrete caused by track equipment is solely the responsibility of the Contractor and no extra payment will be made.

End of Addendum No. 2