

Pyramid Water Tank, Phase I - Tank Improvements

Contract No. 0708-166

Bids Opened: December 20, 2007

			Bidder No. 1		Bidder No. 2		Bidder No. 3	
			Granite Construction Company		RDC, Inc. dba Resource Development Company		Sierra Nevada Construction, Inc.	
The apparent low bidder is Bidder No. 2 (RDC, Inc. dba Resource Development Company)								
Bonding Provided			5%		5%		5%	
Bidder Acknowledges Receipt of Addendums			yes		yes		yes	
Affidavit of Preferential Bidders Status			has		has		has	
Description	Scheduled		Unit	Total	Unit	Total	Unit	Total
	Value	Unit	Price	Price	Price	Price	Price	Price
1 Mobilization, Bonds, Insurance, and Permits (see Note 2 Below).	1	LS	67,892.00	67,892.00	29,900.00	29,900.00	43,007.00	43,007.00
2. Dust Control, Traffic Control, SWPPP, Erosion & Sediment Controls, and all associated work.	1	LS	20,000.00	20,000.00	1,000.00	1,000.00	2,500.00	2,500.00
3. Vault to Tank Piping consisting of approximately 266 lf of 24" D.I.P., 40 lf of Steel Piping with two 90° Steel Elbows FBEC, two EBAA Flex-tend 424M21, 5 - 24" D.I. Angle MJ Fittings, two 25.80" Coupling, two 24" Bray Butterfly Valves, 42 lf 2" PVC, 14 lf 2" Sch 40 Steel Pipe, 14 - 24" Megalugs, 4 Mega flanges, Concrete Thrust Blocks, Concrete Pipe Encasements, and all associated work.	1	LS	275,000.00	275,000.00	222,300.00	222,300.00	175,000.00	175,000.00
4. Tank Subgrade preparation and compaction, Aggregate Base and Sand under Tank, and all associated work.	1	LS	50,000.00	50,000.00	56,000.00	56,000.00	30,000.00	30,000.00
5. Approximately 446 lf of Concrete Ring Wall Foundation a minimum of 18 inches in width and a minimum of 30 inches deep, reinforcement, and all associated work.	1	LS	50,000.00	50,000.00	55,200.00	55,200.00	50,000.00	50,000.00
6. Approximately 15840 sf of welded steel tank flooring, and all associated work.	1	LS	300,000.00	300,000.00	229,600.00	229,600.00	260,000.00	260,000.00
7. Approximately 10710 sf of 24 ft high welded steel tank wall, and all associated work.	1	LS	400,000.00	400,000.00	327,000.00	327,000.00	410,000.00	410,000.00
8. All Steel Columns and Roof Rafters, and all associated work.	1	LS	115,000.00	115,000.00	70,100.00	70,100.00	105,000.00	105,000.00
9. Approximately 14530 sf of welded steel roofing plus approximately 2100 sf of 3 foot radius roof knuckle, and all associated work.	1	LS	230,000.00	230,000.00	194,000.00	194,000.00	214,000.00	214,000.00
10. Tank Overflow, Hatches, Vents, Manways, Ladder, Handrails, Electrical Conduit, and all associated work.	1	LS	75,000.00	75,000.00	25,000.00	25,000.00	70,000.00	70,000.00
11. Tank Interior & Exterior Blasting, Cleaning, Coatings, and all associated work.	1	LS	275,000.00	275,000.00	334,000.00	334,000.00	250,000.00	250,000.00
12. Tank Clean-out, Disinfecting, Filling, Testing, and all associated work.	1	LS	5,000.00	5,000.00	4,000.00	4,000.00	4,000.00	4,000.00
13. Tank Electrical, Intrusion, Panel, and all associated work.	1	LS	5,000.00	5,000.00	2,800.00	2,800.00	6,000.00	6,000.00
14. Approximately 14,400 sf of 6" Type I, Class "A" 1-1/2" Aggregate Base around Tank and Tank Access Road from tank to gate, and all associated work	1	LS	15,000.00	15,000.00	18,900.00	18,900.00	15,000.00	15,000.00
15. Clean-up and De-mobilization, and all associated work.	1	LS	10,000.00	10,000.00	2,000.00	2,000.00	1,500.00	1,500.00
16. Total Bid Price			\$1,892,892.00		\$1,571,800.00		\$1,636,007.00	
Total Bid Price Written in Words? y/n			yes		yes		yes	
Bidder Information Provided			yes		yes		yes	
Licensing Information Provided			yes		yes		yes	
Disclosure of Principals Provided			yes		yes		yes	
Referenced Provided			yes		yes		yes	
Debarment & Safety Information Provided			yes		yes		yes	
Labor and Equipment Rate Schedules Provided			yes		yes		yes	
Subcontractors Listed			yes		yes		yes	
Proposal Summary Executed			yes		yes		yes	