

Addendum No. 2

2008 Pump Station Rehabilitation Project

Contract No. 0708-248
PWP #WA-2008-220

The following information, clarifications, changes and modifications are by reference incorporated into the bid documents for the above referenced project. Any work item or contract provision not changed or modified will remain in full force and effect. The bid date and time and construction schedule remain the same.

- 1. Question:** What size and end connection is the TMWA provided PRV to be installed at the Huffacre Pump Station?
Response: 2.5 inches with flanged ends (150 lb bolt pattern).
- 2. Question:** On drawing C-8 Note 2 refers to "Nuts and bolts to be protected from overspray and/or brush applied paint, or any coatings." What about the existing nuts and bolts that already have coatings on them? Also this is a very labor intensive process, and we just want to clarify that this is what you want?

Response: All of the nuts and bolts, regardless of whether an existing coating has been applied shall be protected from new/additional coatings. We realize this will be very labor intensive and it is being done to reduce the effort needed to remove them and we do not want there removal at a later time to cause localized cracks in the new coating being added.

Attachments:

Pages 1 through 1: Contract Specification and Contract Drawing Addenda Items

TMWA
2008 PUMP STATION REHABILITATION PROJECT
CONTRACT NO. 0708-248
ADDENDUM NO. 2

CONTRACT DRAWINGS		
Addendum Item	Drawing	Location and Description of Change
2.01	E-1	EQUIPMENT SCHEDULE: REDUCE THE QUANTITY NEEDED FOR ITEM NUMBER 2 FROM 2 TO 1
2.02	E-3	DETAIL D/D3: ELIMINATE THE ELECTRICAL SERVICE JUNCTION BOX REPLACEMENT ADDITION (ES/2)
2.03	C-7	NOTES FOR SHEET C7: ADD THE FOLLOWING "9. REMOVE ALL SURFACE RUST AND RECOAT EXISTING ELECTRICAL SERVICE JUNCTION BOX (NOT SHOWN) PER SYSTEM F OF THE PAINT SCHEDULE. COLOR TO MATCH EXISTING.

END OF ADDENDUM NO. 2 FOR TECHNICAL SPECIFICATIONS AND CONTRACT DRAWINGS