

## Chalk Bluff Parallel Siphon

Contract No. 0910-176

Bids Opened: January 14, 2010

		Bidder No. 1		Bidder No. 2		Bidder No. 3		Bidder No. 4		Bidder No. 5		Bidder No. 6		Bidder No. 7		Bidder No. 8			
		Reno Tahoe Construction, Inc.		Gerhardt & Berry Construction, Inc.		Q & D Construction, Inc.		Gradex Construction Company		Aspen Developers Corp		Peavine Construction, Inc.		A & K Earth Movers, Inc.		MKD Construction, Inc.			
Bonding Provided		5%		5%		5%		5%		5%		5%		5%		5%			
Bidder Acknowledges Receipt of Addendums		yes		yes		no		no		yes		yes		yes		yes			
Affadavit of Preferential Bidders Status		n/a		n/a		n/a		n/a		n/a		n/a		n/a		n/a			
Description	Scheduled	Unit	Unit	Total	Unit	Total	Unit	Total	Unit	Total	Unit	Total	Unit	Total	Unit	Total	Unit	Total	
	Value		Price	Price	Price	Price	Price	Price	Price	Price	Price	Price	Price	Price	Price	Price	Price	Price	
1. Mobilization, Bonds, and Insurance (See Note 2)	1	LS	7360.57	7,360.57	25,495.00	25,495.00	16,615.00	16,615.00	12,000.00	12,000.00	20,000.00	20,000.00	11,400.00	11,400.00	35,000.00	35,000.00	28,800.00	28,800.00	
2. Demobilization and Cleanup	1	LS	1256.96	1,256.96	2,944.00	2,944.00	5,405.00	5,405.00	42,000.00	42,000.00	5,000.00	5,000.00	8,000.00	8,000.00	3,630.00	3,630.00	5,000.00	5,000.00	
3. Installation of 40 LF of 54-in Sch 40 (Flg x PE) MLS and connection to existing siphon inlet.	40	LF	778.1	31,124.00	497.35	19,894.00	245.00	9,800.00	0.00	0.00	600.00	24,000.00	156.00	6,240.00	500.00	20,000.00	500.00	20,000.00	
4. Purchase and installation of 54-in Stainless Steel Sluice Gate and actuator in existing siphon inlet.	1	LS	23246.85	23,246.85	20,182.00	20,182.00	19,150.00	19,150.00	20,000.00	20,000.00	20,000.00	20,000.00	23,825.00	23,825.00	19,300.00	19,300.00	23,000.00	23,000.00	
5. Fusion and Installation of 54-in HDPE pipe and fittings, including: trenching, bedding, backfill, 2-in Sch 40 PVC conduits, 6-in HDPE perforated drain lines and geotextile stabilization as called for on the Drawings.	550	LF	143.05	78,677.50	157.80	86,790.00	195.00	107,250.00	345.00	189,750.00	275.00	151,250.00	395.00	217,250.00	280.00	154,000.00	525.00	288,750.00	
6. Fusion and Installation of 2-54-in HDPE pipes and fittings, including: trenching, bedding, backfill, 2-in Sch 40 PVC conduits, 6-in HDPE perforated drain lines and geotextile stabilization as called for on the Drawings.	90	LF	290.81	26,172.90	266.00	23,940.00	870.00	78,300.00	260.00	23,400.00	425.00	38,250.00	195.00	17,550.00	633.00	56,970.00	425.00	38,250.00	
7. Construction of Outlet Structure and miscellaneous grading and discharge improvements at siphon outlet.	1	LS	31034.16	31,034.16	36,061.00	36,061.00	35,950.00	35,950.00	27,180.00	27,180.00	30,000.00	30,000.00	42,500.00	42,500.00	39,900.00	39,900.00	40,000.00	40,000.00	
8. Installation and maintenance of BMP's and pumping facilities for temporary diversion of Chalk Creek drainage flows around project improvements.	1	LS	2538.98	2,538.98	8,220.00	8,220.00	4,300.00	4,300.00	18,000.00	18,000.00	5,000.00	5,000.00	13,500.00	13,500.00	21,200.00	21,200.00	18,000.00	18,000.00	
9. Installation of 2 ft depth of 12" – 18" rip-rap at siphon outlet transition.	200	SF	3.53	706.00	3.80	760.00	10.75	2,150.00	3.50	700.00	10.00	2,000.00	7.00	1,400.00	10.00	2,000.00	6.00	1,200.00	
<b>Total Bid Price</b>				<b>\$202,117.92</b>		<b>\$224,286.00</b>		<b>\$278,920.00</b>		<b>\$333,030.00</b>		<b>\$295,500.00</b>		<b>\$341,665.00</b>		<b>\$352,000.00</b>		<b>\$463,000.00</b>	
Total Bid Price Written in Words? y/n				yes		yes		yes		yes * total corrected		yes		yes		yes		yes	
Bidder Information Provided				yes		yes		yes		yes		yes		yes		yes		yes	
Licensing Information Provided				yes		yes		yes		yes		yes		yes		yes		yes	
Disclosure of Principals Provided				yes		yes		yes		yes		yes		yes		yes		yes	
Referenced Provided				yes		yes		yes		yes		yes		yes		yes		yes	
Debarment & Safety Information Provided				yes		yes		yes		yes		yes		yes		yes		yes	
Labor and Equipment Rate Schedules Provided				yes		yes		yes		yes		yes		yes		yes		yes	
Subcontractors Listed				yes		yes		no		yes		yes		yes		yes		yes	
Proposal Summary Executed				yes		yes		yes		yes		yes		yes		yes		yes	